

S2387: Commissioning the UCN source with beam

Ruediger Picker
for the TUCAN collaboration

01-May-2024

Close-up view of UCN source

Contents:

- Intro
- Status
- Plans


- The TRIUMF UltraCold Advanced Neutron (TUCAN) source is a **spallation-driven superfluid-helium, superthermal source**.
- Its goals are
 1. To provide record amounts of ultracold neutrons to the TUCAN EDM experiment
 2. To establish a UCN user facility at its second port.
- Installation and cryogenic commissioning **has started**.
- We are working very hard to make **UCN production in 2024** possible.




C. Bidinosti², M. Bradley¹⁶, A. Brossard³, C. Davis³, D. Fujimoto³, M. Gericke⁴, P. Giampa³, R. Golub⁵, S. Hansen-Romu⁴, K. Hatanaka⁶, T. Hayamizu⁷, T. Higuchi⁸, G. Ichikawa⁹, S. Imajo¹⁰, A. Jaison¹¹, B. Jamieson², S. Kawasaki⁹, M. Kitaguchi¹², W. Klassen¹³, A. Konaka³, E. Korkmaz¹⁴, E. Korobkina⁵, M. Lavvaf⁴, L. Lee³, T. Lindner³, K. Madison¹³, Y. Makida⁹, R. Mammei², J. Mammei⁴, J. Martin², R. Matsumiya³, M. McCrea², E. Miller¹³, K. Mishima¹⁵, T. Momose¹³, T. Okamura⁹, H. Ong¹⁰, R. Picker³, D. Ramsay³, W. Schreyer³, H. Shimizu¹², S. Sidhu³, S. Stargardter⁴, I. Tanihata⁶, S. Vanbergen¹³, W. vanOers³, Y. Watanabe⁹, A. Zahra¹¹

1 - Nagoya University, 2 - UW, Winnipeg, Canada, 3 - TRIUMF, Vancouver, Canada, 4 - UofM, Winnipeg, Canada, 5 - NCSU, Raleigh, NC, USA, 6 - RCNP, Osaka, Japan, 7 - RIKEN, 8 - KURNS, Kyoto University, Kyoto, Japan, 9 - KEK, Tsukuba, Japan, 10 - RCNP, Osaka University, 11 - University of Manitoba, 12 - Nagoya University, Nagoya, Japan, 13 - UBC, Vancouver, Canada, 14 - UNBC, Prince George, Canada, 15 - KEK, Tokai, Japan, 16 – University of Saskatchewan, Saskatoon, Canada

1. **480 MeV protons** on tungsten create **spallation neutrons**
2. lead, graphite and **heavy water** moderate fast neutrons (MeV) to thermal neutrons (25 meV)
3. **liquid deuterium** at 20 K moderates further to create a **large cold flux** (1 meV)
4. **^4He** at around 1 K **converts** 1 meV (9Å) neutrons **to UCN** (< 215 neV)



1. **480 MeV protons** on tungsten create **spallation neutrons**
2. lead, graphite and **heavy water** (300 K) **moderate** fast neutrons (MeV) to thermal neutrons (25 meV)
3. **liquid deuterium** at 20 K moderates further to create a **large cold flux** (1 meV)
4. **^4He** at around 1 K **converts** 1 meV (9Å) neutrons **to UCN** (< 215 neV)
5. **Extraction to experiments via material guides**



UCN source cryogenic testing

- Oct 2023: He cryostat connected to liquefier and cooled down to 4.2 K
- Dec 2023: He cryostat cooled down to 1.09 K using large subatmospheric pumps and short prototype of main heat exchanger

Why is it imperative to produce UCN this fall?

1. The Canadian part of the collaboration is submitting a **CFI proposal** beginning of 2025 and need to have demonstrated the source capabilities.
2. The Japanese part is submitting a **proposal to JSPS** in June (too early) but the review meetings for the grant are happening late fall.

EDM

- Magnetically shielded room completed
- Thorough characterization showed deficiency in shielding factor: 10 000 vs 50 000
- Producer agreed to install additional layer inside the MSR
- Completion: August 2024
 - redesign of main holding field B0 coil necessary
 - Completion towards end of 2024
 - Laser enclosure for magnetometer and comagnetometer lasers next to MSR in construction as well as Ambient Magnetic Compensation coil

Top view of
UCN area
(April 4, 2024)



proton beamline

target

He pumps


Cryostat

LHE supply and return lines


slow control

Gravity, lifetime,
decay...


EDM
experiment



- 6 layer vessel
 1. Superfluid vessel, UCN production volume, cryogenic guide
 2. Vacuum separation wall (withstands D₂ explosion, 21 bar)
 3. Inner wall of LD2 vessel
 4. Out wall of LD2 vessel
 5. Thermal radiation shield
 6. Vacuum vessel
- All welded due to lack of space for flanges
- Passive, except temperature sensors and heaters
- We received go-ahead for production Oct 2023
- Installed and connected in April 2024
- Heroic effort by Cam Marshall and machine shop!



Tail section manufacturing



Wall 1: UCN prod volume



Wall 2: vacuum separation



Wall 2



Wall 2



Wall 3:
inside wall of LD₂ vessel



Wall 4:
outside LD₂ wall



Wall 4



Wall 4




Wall 5:
thermal radiation shield



Wall 6: vacuum vessel
plus wall 5 superinsulation



The machine shop crew with the completed tail section



Tail section installation 1







Tail section installation 2




Tail section installed ...



... and connected





2.5 m

He pumps

He cryostat

Vacuum pumps

LD2 cryostat


Tail section
(LD₂ and LHe)

Shielding

Main heat exchanger

Source
commissioning
setup: just vacuum
separation foil and
detector inside
shielding





Tail section (LD₂ and LHe)

Shielding

LD2 cryostat

Main heat exchanger

He cryostat

He pumps

Vacuum pumps

Source commissioning setup: just vacuum separation foil and detector inside shielding

Source

- Reconnect all He cryostat connections
- Install, pipe and test ^3He gas system
- Complete slow control
- Test source with $^3\text{He} \Rightarrow <1 \text{ K} \Rightarrow$ **June**
- Install large HEX1 and UCN guide
- Pipe and test isopure helium gas system
- Complete its slow control
- Condense and cool helium inside UCN production volume \Rightarrow **August**
- Install UCN guides and detector
- Produce UCN \Rightarrow **September**

BL1U

- Reconnect target water cooling system
- Complete shielding and safety systems
- Perform BL1U commissioning to 40 μA
 \Rightarrow **June to September**
- Ready for UCN production

Sounds simple, but we identified at least 99 individual tasks to get there!

LD2 moderator deferred to 2025.

⇒ **scheduled for September 24 to Oct 1, 2024**


First UCN production and source characterization Sept 24 to Oct 1

Investigation of neutron yield and UCN storage lifetime in the source as a function of

- Proton current (1 – 40 μA)
- Irradiation duration (few s to few min)
- Temperature of superfluid helium (0.8 K to 1.6 K)


Also production during detection.

⇒ Compare with predictions from simulations!



Experiment procedure:

1. Produce UCN with valve just outside source closed
 2. Stop UCN production, keep valve open
 3. Open valve to detect UCN
- Vary durations of 1 and 2.



⇒ **scheduled for September 24 to Oct 1, 2024**

First UCN production and source characterization Sept 24 to Oct 1

Investigation of neutron yield and UCN storage lifetime in the source as a function of

- Proton current (1 – 40 μA)
- Irradiation duration (few s to few min)
- Temperature of superfluid helium (0.8 K to 1.6 K)


Also production during detection.

⇒ Compare with predictions from simulations!


Experiment procedure:

1. Produce UCN with valve just outside source closed
2. Stop UCN production, keep valve open
3. Open valve to detect UCN

Vary durations of 1 and 2.




Very important for CFI/JSPS proposals.




⇒ spring 2024

- Repeat program from before, now with LD2.



Phase 7: extraction out of the biological shielding



Gas panels

Radiation Shielding

Slow control

5.5 m

EDM/MSR


2nd port

placeholder

⇒ summer 2024

Possible experimental program:

- Transmission and storage lifetime with
 - different vacuum separation foil sizes and thicknesses inside the superconducting polarizer
 - Various neutron handling components
- Polarization transport
- Detector tests



29 days of UCN runs in 2028 – 28 different configurations

For the EDM commissioning, we will submit a new proposal.



We have made significant progress and are on track for UCN production this year!

What we would like from the PP EEC:

- review and (hopefully) endorsement of our plans
- acknowledgement about the importance to produce UCN this year



TUCAN

TRIUMF Ultra Cold
Advanced
Neutron source

Questions?



[360 degree fly over TUCAN](#)



[360 degree walk through TUCAN source](#)

Shutdown and beam related


- Block migration into Meson hall: May 15-17 (22-24?)
- Moving UCN blocks inside: right after
- PIF run, limited PIF roof access: May 24 to Jun 2
- BL1A startup: June 4
- First BL1U beam: June 19

Cryogenic and source dates

- 3AS, 3BS cooldowns June 2024
- 3BL July 2024
- 5 August 2024
- UCN production Sept 24 – Oct 1

Beam development shifts:

1	Date	Shift(s)	Plan
2	Fri June 14, 2024	DAY, EVE	Commission 1VM5 Beam Halo Monitor, investigate high BSM55 spill levels
3	Wed, June 19 2024	DAY	Re-establish BL1U beam on target (DC, 1 uA), then ramp up current to 5 – 10 uA, commission BPMs, perform RPG surveys at 1, 5 and 10 uA
4	Fri, June 28	DAY	see above
5	Thu, July 4 2024	DAY	Find optimal beam tune for BL1U and BL1A using the UCN kicker, TNIM calibrations kicking and commissioning new kicker sequencing mode
6	Thu, Aug 1 2024	DAY	see above
7	Thu, Aug 8 2024	DAY	see above
8	Thu, Aug 15 2024	DAY	Commission TPM, determine TPM calibration using knife edge method
9	Fri, Aug 23 2024	DAY	see above
10	Thu, Sep 12 2024	DAY	ramp up BL1U current to 40 microA, perform RPG surveys at 10, 20 and 40 uA



Shielding

He cryostat


2.3 m

Cryo connection box

He pumps

Vacuum pumps





LD₂ cryostat
cools down D₂ to 20 K at 65 W heat input

³He cryostat
cools down HEX to 0.89 K at 9.6 W heat input

1.1-K ⁴He
converts CN to UCN

Polarizer, vacuum sep foil
only one UCN spin state is transmitted

20-K LD₂
creates cold flux

300-K D₂O
creates thermal flux

graphite
reflects neutrons

steel
shielding

Lead
reduces γ -heating of superfluid

³He

⁴He

Magnetic potential 60 neV/T
3.7 T field creates barrier of 220 neV

EDM

W Target
creates spallation neutrons


Superfluid heat conduction channel
removes cryostat from intense radiation

Main ³He/⁴He heat exchanger
cools down isopure ⁴He to 1 K at 10 W heat input

2.5 m


Similar basic layout with major improvements:

Parameter	Prototype source	Next gen source
Beam current	1 μA	40 μA (480 MeV)
Production volume	8 L	27 L
Cold moderator	sD ₂ O	LD ₂
Production rate	$2 \times 10^5 / \text{s}$	$1.4\text{-}1.6 \times 10^7 / \text{s}$ ($500 \text{ s}^{-1} \text{cm}^{-3}$)



Similar basic layout with major improvements:

Parameter	Prototype source	Next gen source
Beam current	1 μA	40 μA (480 MeV)
Production volume	8 L	27 L
Cold moderator	sD ₂ O	LD ₂
Production rate	$2 \times 10^5 / \text{s}$	$1.4 - 1.6 \times 10^7 / \text{s}$ ($500 \text{ s}^{-1} \text{cm}^{-3}$)
Cooling power	0.3 W	10 W
He-II temperature	0.9 K	1.1 – 1.15 K
Extraction	Vertical by 1.2 m	Near horizontal 0.3 m up
Vacuum separation	No foil	Warm vacuum sep foil + B field
Position of cryostat	On top of source	2.5 m away





from KEK/RCNP, Japan

3 cooling stages, heat exchanger to cool isopure ^4He UCN converter



- ^1He bath cryostat (4.5 K)
- ^4He pumping section (1.4 K)
- ^3He pumping section (down to 0.8 K)
- Isopure ^4He UCN converter cooled via heat exchanger

⇒ Running nominally at 1 μA beam (as at RCNP).





Parameter	Prototype source	Next gen source
Beam current	1 μ A	40 μ A (480 MeV)
Production volume	8 L	27 L
Cold moderator	sD ₂ O	LD ₂
Production rate	2×10^5 /s	$1.4 - 1.6 \times 10^7$ /s ($500 \text{ s}^{-1} \text{ cm}^{-3}$)
Cooling power	0.3 W	10 W
He-II temperature	0.9 K	1.1 – 1.15 K
Extraction	Vertical by 1.2 m	Near horizontal 0.23 m up
Vacuum separation	No foil	Warm vacuum sep foil + B field
Position of cryostat	On top of source	2.5 m away behind shielding



EDM Experiment	published				future			
	ILL- RAL- Sussex	PSI nEDM	PSI n2EDM*	LANL EDM**	panEDM stage I***	panEDM stage II***	TUCAN OC100****	TUCAN 2C200****
UCN detected per cycle	14 000	15 000	121 000	78 000	51800 ^x	1 380 000 ^x	846 000	1 420 000
Size	20 l	20 l	116 l	40 l	34 l	34 l	31.5 l	63 l
Density detected (1/cc)	0.7	0.75	1	2	1.5 ^x	40 ^x	27	23
Publication	(1)	(2)	(2)	(3)	(4)	(4)		(5)

Bottom cell
only

- * expected, based on PSI nEDM.
- ** expected, based on storage expts.
- *** estimation based on loss factors
- **** expected, extensive MC.
- ^x at end of Ramsey cycle

Steve Sidhu
Source and EDM optimization
Tuesday, 10:50 am

Publications:

- (1) C.A. Baker, et al, 2006: <http://dx.doi.org/10.1103/PhysRevLett.97.131801>
- (2) G. Pignol, et al, 2021: <https://doi.org/10.21468/SciPostPhysProc.5>
- (3) T. Ito et al, 2020: <http://dx.doi.org/10.1103/PhysRevC.97.012501>
- (4) D. Wurm, 2021: <https://mediatum.ub.tum.de/doc/1631520/1631520.pdf>
- (5) S. Sidhu et al, 2022: <https://doi.org/10.1051/epjconf/202328201015>


Some relevant numbers (compared to inverse geometry source)

TUCAN source (engineering stage)

- Production $1.4-1.6 \times 10^7$ UCN/s
- Source helium temp 1.03 K to 1.13 K
- Cooling power 10 W (3He fridge)
- Source storage lifetime 28 s
- Figure of merit $P\tau = 4.5 \times 10^8$
- Density in the source 3×10^3 UCN/cc
- Total number in the source 3×10^8 UCN
- Initial density in 70 l EDM expt 200 UCN/cc
- Counted at the end of cycle 2×10^6


Inverse geometry source (conceptual stage)

- Production 1.8×10^9 UCN/s
- Source helium temp 1.6 K
- Cooling power 100 W (4He fridge)
- Source storage lifetime 2 s
- Figure of merit $P\tau = 3.6 \times 10^9$
- Density in the source 5×10^4 UCN/cc
- Total number in the source 6.5×10^9 UCN
- Initial density in 100 l perfectly matched expt 10000 UCN/cc



<https://arxiv.org/abs/1905.09459>

TUCAN source layers



Gas panels

Radiation Shielding

Slow control

5.5 m

placeholder



He cryostat

He pumps


Radiation Shielding

Gas panels

Slow control

placeholder

5.5 m



Cryo connection box

Shielding

He cryostat

Vacuum pumps


He pumps

Slow control

Gas panels

placeholder

5.5 m



2.5 m

Tail section
(LD₂ and LHe)

Shielding

LD2 cryostat

He cryostat

He pumps

Vacuum pumps

