



中国科学院  
CHINESE ACADEMY OF SCIENCES



中国科学院近代物理研究所  
Institute of Modern Physics, Chinese Academy of Sciences

**IUPAP WG9/C12 AGM and Nuclear Science Symposium 2026**

# **HIAF status and beam commissioning**

**Zhiyu Sun**

**Institute of Modern Physics, CAS**

**2026/04/15**

# Outline

---

- 1. General introduction**
- 2. Construction and beam commissioning**
- 3. Future plan**
- 4. Conclusion**

# 1. General introduction

One of the major national science and technology infrastructure in China, with a total budget of **2.8 billion CNY** and a construction period from **2018 to 2025**.




## Where is the HIAF?

Located in **Huizhou of Guangdong Province**, strategically situated close to Shenzhen, Hong Kong, and Guangzhou. Share the campus with CiADS.

# 1. General introduction

## HIAF: High-Intensity heavy-ion Accelerator Facility

The HIAF project consists of a superconducting ECR ion source (SECR), a superconducting CW heavy ion beam linac (iLinac), a fast ramping rate synchrotron (BRing) and 6 experimental terminals



- ① Low energy nuclear structure terminal
- ② High energy experimental terminal
- ③ High energy fragment separator HIRIBL
- ④ High precision spectrometer ring SRing
- ⑤ Electron ion recombination terminal
- ⑥ Radioactive ion beam physics terminal

# 1. General introduction

## Beam parameters and features

- High current low energy **CW** heavy-ion beams provided by iLinac
- highest intensity **pulsed** heavy-ion beams provided by BRing

	<b>SECR</b>	<b>iLinac</b>	<b>BRing</b>	<b>HIRIBL</b>	<b>SRing</b>
<b>Energy (MeV/u)</b>	0.014 ( $U^{35+}$ )	17 ( $U^{35+}$ )	835 ( $U^{35+}$ )	800 ( $U^{92+}$ )	1100 ( $U^{92+}$ )
<b>Magnetic rigidity (Tm)</b>	---	---	34	25	15
<b>Beam intensity of U</b>	<b>1.7 emA</b> ( $U^{35+}$ )	<b>1.0 mA</b> ( $U^{35+}$ )	<b><math>1 \times 10^{11}</math>ppp</b> ( $U^{35+}$ ) <b><math>3 \times 10^{11}</math>pps</b> ( $U^{35+}$ )	-----	<b><math>(2-5) \times 10^{11}</math>ppp</b> ( $U^{92+}$ )
<b>Operation mode</b>	DC	CW or pulse	fast ramping (12T/s, 3Hz)	Momentum-resolution 1100	DC, deceleration
<b>Emittance or Acceptance</b> (H/V, $\pi \cdot \text{mm} \cdot \text{mrad}$ , dp/p)		5 / 5	200/100, 0.5%	$\pm 30 \text{mrad(H)}/\pm 15 \text{mrad(V)}$ , $\pm 2\%$	40/40, 1.5% (normal mode)

## 2. Construction and beam commissioning




### Civil construction

10 above-ground building and a **2 km long underground tunnel** at a depth of 13 meters



## 2. Construction and beam commissioning

### Installation schedule



The first dipole was moved into the tunnel in 27<sup>th</sup> March, 2024



iLinac was installed into tunnel in Sept. 2025





The first beam was accelerated in BRing on 27<sup>th</sup> October, 2025

## 2. Construction and beam commissioning

### Superconducting ECR ion source for highly charged ions

- 3<sup>rd</sup> (28 GHz) and 4<sup>th</sup> (45 GHz) superconducting ECR ion source are installed

A highly charged heavy ion could be created with high magnetic field and high microwave frequency




- **Bi<sup>35+</sup>**: DC beam current is about 350 eμA , the new record of Bi ion.
- **Bi<sup>31+</sup>**: peak current is 1 emA with the afterglow operation mode.

## 2. Construction and beam commissioning


### RFQ and SRF Linac

- Normal conducting RFQ is used to accelerated ions to 0.8 MeV/u
- SRF CW linac is used to accelerated  $U^{35+}$  to 17 MeV/u ( $O^{6+}$  to 33 MeV/u)



$^{209}\text{Bi}^{31+}$  commissioning:

- ◆ RFQ run at full power: 100kW 3ms@5Hz
- ◆ SRF power: QWR@25MV/m; HWR@28MV/m




Gradient of iLinac cavities


## 2. Construction and beam commissioning

### B Ring with a dipole magnetic field ramping rate of 12 T/s

Because of the space charge and dynamic vacuum effects, heavy ion beams should be launched to the high energy as soon as possible



Repetition rate: 3-5 Hz, 5-10Hz



B Ring accelerator tunnel


### - Challenges

- High current ramping rate up to **38 kA/s** for dipole PS, drive 12 T/s dipoles
- High acceleration voltage up to **240 kV/turn**, satisfy to energy gain/turn
- Thin wall vacuum chamber less than **0.3 mm**, avoid distortion with eddy current

## 2. Construction and beam commissioning

### Fast ramping rate full energy storage power supply

Requirement of magnet power converters featured by fast ramping rate: 12T/s,  $\pm 38000\text{A/s}$ , the peak power reaches 230MW totally at full load



---Expert Evaluation on 28/09/25

...which fully **satisfy the excitation current specifications** of pulse and DC power supplies for the HIAF facility.



**Dipole power supply**

- Energy **capacitor** is used to **store energy** during the falling, and provide the energy for next fast ramping
- Achieved leading level performance, and power consumption largely **reduces to 10%**

# 2. Construction and beam commissioning

## Magnetic alloy core loaded RF system

Developed large-size nan-crystalline magnetic alloy rings,  $\mu Qf$  value has reached the highest world level.





Total RF voltage is 350 kV in HIAF

Facilities	Voltage (kV)	Length (m)	Gradient (kV/m)
JPARC-RCS	41	1.78	23
SIS18	50	2	25
HIAF-BRing	<b>70</b>	<b>2</b>	<b>35</b>



---Expert Evaluation on 16/10/25

The measured results of the HIAF high-frequency system have all met the design specifications. ... internationally advanced and **satisfies the design requirements of the HIAF facility's high-frequency system.**




## 2. Construction and beam commissioning

### Titanium alloy-lined thin-walled vacuum chamber

**Problem:** fast ramping of the magnets induces eddy currents:

- The chamber walls are heated
- Generation of additional harmonics in field




IMP: thin-wall chamber supported by rings

---Expert Evaluation on 26/09/25



Static average vacuum in 570m ring

$4.7 \times 10^{-12}$  mbar



...which delivers the **highest vacuum level** among comparable large international accelerators in operation, offering a key guarantee **for high-brightness, long-lifetime beam operation.**

## 2. Construction and beam commissioning


### The first beam commissioning on October 27<sup>th</sup>, 2025

- $^{18}\text{O}^{6+}$  beam was accelerated up to 2.6 GeV/u with peak current of  $3 \times 10^{11}$  ppp
- the 2 km-long accelerator was successfully commissioned in just **ONE day**



The first beam was injected, accelerated in BRing in 27<sup>th</sup> October, 2025



Projectile	SCL		BRing	
	$E_{\text{proj.}}$ (MeV/u)	$I$ (pμA)	$E_{\text{proj.}}$ (GeV/u)	$I$ (ppp)
$^{18}\text{O}^{6+}$	~33	~35pμA	2.6	$2.5 \times 10^{11}$
$^{209}\text{Bi}^{31+}$	~17	~8.3pμA	0.85	$3.0 \times 10^{10}$




## 2. Construction and beam commissioning

### Beam intensity

- The pulsed particle number of  $O^{6+}$  and  $Bi^{31+}$  beams has exceeded the highest beam intensity record of SIS-18 at GSI
- 4D phase (H & V) painting injection gain factor larger than 60
- Intensities of all ion beams will exceed  $10^{11}$  ppp by 2030



## 2. Construction and beam commissioning



**Spectrometer Ring**  
 Circumference: 273 m  
 Rigidity: 15 Tm

### Operation modes

- Isochronous mode
- Normal Mode
- Internal-target Mode






## 2. Construction and beam commissioning

### Commission run for Schottky mass measurement in SRing

Primary beam:  $^{209}\text{Bi}^{31+}$   $\sim 546$  MeV/u, particle number:  $10^{10}$  ppp every 3 seconds


10 mm-Graphite target

Hot beam from HIRIBL, 1/3 Hz



## 2. Construction and beam commissioning


### Commission run for Schottky mass measurement in SRing



## 2. Construction and beam commissioning




### Commission run for Schottky mass measurement in SRing




## 2. Construction and beam commissioning

### Commission run for Schottky mass measurement in SRing



## 2. Construction and beam commissioning

### Commission run for Schottky mass measurement in SRing



$$\frac{\sigma(m)}{m} \sim \frac{11 \text{ keV}}{202 u} \sim 5.8 \times 10^{-8}$$

## 2. Construction and beam commissioning



### Electron cooling




First beam cooling test with 81 MeV/u  $\text{Bi}^{31+}$ :

Isochronous mode:

Momentum spread before cooling :  $3 \times 10^{-3}$

After cooling (total):  $1 \times 10^{-4}$


450 kV electron cooler



Cooling process in longitudinal Schottky

### Electron ion recombination terminal

Use separated electron cooler and electron target, to measure the dielectronic recombination rate with a wide CM range and high precision.



60 kV electron target

## 2. Construction and beam commissioning



### Gas-filled recoil spectrometer



SC solenoid instead of quadrupole magnets to get better acceptance

DSSD Energy Resolution: 30 keV  
Si-box Det. Efficiency: 86% ( $\alpha$  source)  
MWPC Det. Efficiency: 99.8% ( $\alpha$  source)

### High rigidity fragment separator (HIRIBL)




HFRS Parameters	
$B\rho_{\max}$	15~25Tm
$P/\Delta P$	750,700,1100
$\Delta B\rho$	$\pm 2.0\%$
$\Delta\Omega$	$\pm 30$ mrad(x) $\pm 20$ mrad(y)
Beam spot $\Delta\Phi$	$\pm 1$ mm(x) $\pm 2$ mm(y)



### 3. Future plan

- Ion beams of Bi, C, Ar, Kr and U will be provided to test the experimental terminals.



- Mostly machine tuning, have the Day-one experiments at appropriate time.
- **Pass the national acceptance inspection, probably in October, 2026**
- Change to normal operation mode, available beam time will reach 3,000 hours in 2028 and ultimately 5,000 hours by 2030

## 4. Conclusion



- **By providing intense heavy-ion beams, HIAF will open new opportunities for science and technology.**
- **The construction work for HIAF has been finished successfully, the first beam commissioning with  $O^{6+}$  and  $Bi^{31+}$  were carried out, and very good results were obtained.**
- **Science cannot advance without good collaboration, as an open, shared, and internationally connected research platform, we sincerely expect that more scientists can join us to explore the scientific potential of this facility and to advance our common goals in nuclear physics.**

# Thanks for your attention!

